

Pre-fabricated Rebar Assemblies



IMPROVE ONSITE PRODUCTIVITY-eliminates time consuming jobsite assembly.



GREATER DIMENSIONAL STABILITY - welded rebar cages hold their dimensions throughout handling & setting.



FAST-away from the construction site under controlled conditions using the MIG welding process. Take rebar assembly off the critical path.

These and other products for, Traffic Control, Solar Panels, Duct Banks, Transformer Pads, Columns & Beams, Carpet Rollmats, give the designer a broad range of options for specifying pre-assembled welded fabrications.

Our welding process is compliant with AWS D1.4 using A706 weldable rebar. IDOT Mil certification provided



Engineers and contractors are seeing the benefits of factory made fabrications.



Owens Supply Company
10025 Clow Creek Dr. Plainfield, IL. 60585-7531
P:1.630.596.9999 F:1.630.596.9995
email:sales@owensupply.com